

# TOWN OF WEST SENECA



ENGINEERING  
DEPARTMENT

TOWN SUPERVISOR  
SHEILA M. MEEGAN  
TOWN COUNCIL  
EUGENE P. HART  
JOHN M. RUSINSKI

April 10, 2013

Honorable Town Board  
Town of West Seneca

**Re: Change order request – Town Pool**

Honorable Board Members,

The building department brought to our attention the need to replace pool infrastructure to ensure continued operation of the pool. All of the piping from the pool filter to the pool pump room is in need of replacement as well as the frame and doors that allow access to the Pool's filter system. The total cost for this work from William L. Watson, Co Inc. is \$64,270 and can be paid for with monies available from previously bonded recreation projects. This amount can be added to the pool rehabilitation project as a change order as that contract is still open. We have reviewed the scope of work and feel the price is reasonable. Please approve this change order.

Very truly yours,

A handwritten signature in black ink, appearing to read "S. R. Tanner", is written over a faint, illegible typed name.

Steven R. Tanner, P.E.  
Town Engineer

cc: Files: TB.  
Project

---

# william l. watson CO, INC.

---

8064 NORTH MAIN STREET • EDEN, NY 14057 • 716-992-3220 • FAX: 992-3862  
EMAIL: [wlwatsonpools@verizon.net](mailto:wlwatsonpools@verizon.net)

March 19, 2013

Town of West Seneca  
45 South Avenue  
West Seneca, N.Y. 14224

Attention: Steve Amoia

Subject: Veterans Park Pool Piping Replacement

Dear Steve:

We offer to replace the piping between the filter tank and the existing pump for \$42,400.

Included in the above pricing:

1. Remove & replace a portion of the chain link fence
2. Saw cutting and removal of concrete decking as required.
3. Excavation and hauling away of excavated material.
4. Replacement of two 10" gate valves and valve boxes.
5. Installing new 10" SCH 80 PVC piping from the two valves into the filter tank and 6" fill line.
6. Installing new 8" SCH 80 PVC section, including new valve between filter tank and existing pool pump.
7. Installing new 8" SCH 80 PVC return to pool piping from pump discharge to the approximate location of 10" valves. This includes all new valves, by-pass piping and chemical injection connections as you currently have.
8. Install new 3" SCH 80 PVC piping from the filter tank to the trash hog pump and the pre-coat line as required.
9. Test all piping.



SWIMMING POOLS ARE OUR BUSINESS

---

# william l. watson CO, INC.

---

8064 NORTH MAIN STREET • EDEN, NY 14057 • 716-992-3220 • FAX: 992-3862  
EMAIL: wlwatsonpools@verizon.net

10. Backfill excavation with compacted #1 and #2 washed stone.
11. Repair of water level control piping and #8 solid ground wire.
12. Installation of 4 inch thick, 4000 psi concrete deck with 6x6x10 mesh reinforcing.


Not included:

1. Draining pool and keeping marcite wet until new 10" valves are installed
2. Repair of any buried electric lines that may be buried where we excavate.

Any questions please call.

Very truly yours,

WILLIAM L. WATSON CO., INC.



David A. Friedrich, President



SWIMMING POOLS ARE OUR BUSINESS

---

*william l. watson* CO, INC.

---

8064 NORTH MAIN STREET • EDEN, NY 14057 • 716-992-3220 • FAX: 992-3862  
EMAIL: [wlwatsonpools@verizon.net](mailto:wlwatsonpools@verizon.net)

March 25, 2013

Town of West Seneca  
45 South Ave.  
West Seneca, N.Y. 14224

Attention: Steve Amoia


Dear Steve:

The cost to cut the existing steel frame work that supports the filter doors and replace with stainless steel is \$12,880.

If you would like to replace the doors at the same time add \$8,990 to the above price.

Very truly yours,

WILLIAM L. WATSON CO., INC



David A. Friedrich, President



SWIMMING POOLS ARE OUR BUSINESS